

Effective Date: March 17, 2000

*SPECIFICATIONS

QUALITY: H-600 HOMESPUN

CONSTRUCTION	-	Pattern Loop
PILE FIBER	-	100% Antron Legacy Nylon with Dura Tech Soil Resistance Treatment
YARN PLY	-	2 Ply
TUFTED YARN WEIGHT	-	28 oz. per sq. yd.
MACHINE GAUGE	-	1/12" (4.72 rows/cm)
STITCHES PER INCH	-	14 (5.51 stitches/cm)
FINISHED PILE THICKNESS	-	.135 inch approx. (3.43 mm)
DENSITY FACTOR	-	7,467
WIDTH	-	12' (3.72 m)
PRIMARY BACKING	-	100% Synthetic
SECONDARY BACKING	-	Power Lock High® Performance Backing
PATTERN REPEAT	-	12" Wide x 12" Long (30.48 cm x 30.48 cm)
FLAMMABILITY	-	Flooring Radiant Panel Test ASTM E-648 - Passes – Has Average Critical Radiant Flux of Greater than .45 Watts per Square Centimeter. Class I. NBS Smoke Chamber (NFDA 258). Has a Maximum Specific Optical Density of 450 or less.

WARRANTIES:

Wear Warranty	-	10 Years
Static Warranty	-	Useful Life
Edge Ravel Guarantee	-	Useful Life
Delamination Guarantee	-	Useful Life
Recycling Program	-	Qualifies for the Invista Reclamation Program

CRI INDOOR AIR QUALITY TESTING PROGRAM – PASSES – CERTIFICATION NO. 14222878

NOTES:

Chair pads are recommended under office chairs with roller casters to preserve appearance retention, act as a deterrent toward delamination and to avoid premature or accelerated wear. Clean Step walk-off tiles by Blue Ridge or walk-off mats are recommended at building entryways to reduce soiling.

*Product specifications are derived from averages resulting from normal manufacturing tolerances in yarn, fiber, fabrication or finishing, and may vary within normal industry tolerances. Construction value quotes are "at point of manufacture". Performance is not affected by these variables.

As with all patterned carpet, a perfect pattern match may not be possible due to the fact that carpet is a textile subject to shrinking and expansion in both length and width. A plus or minus 1% should be expected. However, a reasonable pattern match may be achieved by competent installers using power stretching and stay nailing techniques.

Installation of pattern carpet requires more time to install correctly, which should be considered in the original installation quotation.