

Effective Date: September 17, 2003

\*SPECIFICATIONS

QUALITY: O-400 OPEN PLAN

COLORS:	2109 Cashmere	2113 Moss	2117 Thistle	2121 Gravel
	2110 Oyster	2114 Celadon	2118 Eggplant	2122 Dark Taupe
	2111 Taupe	2115 Olive	2119 Nutmeg	2123 Walnut
	2112 Sand	2116 Laurel	2120 Raisin	2124 Java

CONSTRUCTION	-	Enhanced Precision Cut and Uncut
PILE FIBER	-	100% Antron® Legacy Nylon with Dura Tech Soil Resistance Treatment.
YARN PLY	-	2 Ply
TUFTED YARN WEIGHT	-	38 ozs. per sq. yd. (1153 g/m <sup>2</sup> )
MACHINE GAUGE	-	1/8" (3.15 rows/cm)
STITCHES PER INCH	-	12 (4.72 stitches/cm)
FINISHED PILE THICKNESS	-	.200 inch approx. (5.82 mm)
DENSITY FACTOR	-	6,840
WIDTH	-	12' (3.66m)
PRIMARY BACKING	-	100% Synthetic
SECONDARY BACKING	-	Power Lock® High Performance Backing
ASTM E-648	-	Average Critical Radiant Flux: Greater than .45 - Class 1
NBS SMOKE CHAMBER TEST	-	Specific Optical Density: Less than 450
COORDINATE PRODUCTS	-	Foundation
PATTERN HEIGHT	-	5 1/4" W x 5 1/4 L (13.33 cm W x 13.33 cm L)

WARRANTIES:

Wear Warranty	-	10 Years
Static Warranty	-	Useful Life
Edge Ravel Guarantee	-	Useful Life
Delamination Guarantee	-	Useful Life
Recycling	-	Qualifies for the Invista Reclamation® Program

CRI – INDOOR AIR QUALITY TESTING PROGRAM – Passes – Certification No. 14222878

NOTES:

Chair pads are recommended under office chairs with roller casters to preserve appearance retention, act as a deterrent toward delamination and to avoid premature or accelerated wear. Clean Step® walk-off tiles by Blue Ridge or walk-off mats are recommended at building entryways to reduce soiling.

\*Product specifications are derived from averages resulting from normal manufacturing tolerances in yarn, fiber, fabrication or finishing, and may vary within normal industry tolerances. Construction value quotes are "at point of manufacture". Performance is not affected by these variables.

As with all patterned carpet, a perfect pattern match may not be possible due to the fact that carpet is a textile subject to shrinking and expansion in both length and width. A plus or minus 1% should be expected. However, a reasonable pattern match may be achieved by competent installers using power stretching and stay nailing techniques.

Installation of pattern carpet requires more time to install correctly, which should be considered in the original installation quotation.