

Effective Date: January 21, 2004

*SPECIFICATIONS

QUALITY: R-200 ROCK GARDEN

COLORS:	2034 Celadon	2047 Cashmere	2059 Java
	2426 Thunder	2041 Storm	2051 Shale
	2141 Algae	2427 Pearl	2042 Dune
	2052 Stone	2183 Silver Charcoal	2428 Bracken
	2045 Sienna	2056 Walnut	2425 Shadow
	2429 Pacific		

CONSTRUCTION	-	Multi-Level Pattern Loop
PILE FIBER	-	100% Antron Legacy Continuous Filament Nylon with Dura Tech Soil Resistance Treatment.
YARN PLY	-	2 Ply
TUFTED YARN WEIGHT	-	28 ozs. per sq. yd. (949 g/m ²)
MACHINE GAUGE	-	1/10" (3.94 rows/cm)
STITCHES PER INCH	-	14 (5.51 stitches/cm)
FINISHED TUFTED PILE THICKNESS	-	.152 inch approx. (3.86 mm)
DENSITY	-	6,632
PATTERN REPEAT	-	7 ½" W x 10" L (19.05 cm W x 25.40 cm L)
WIDTH	-	12' (3.66m)
PRIMARY BACKING	-	100% Synthetic
SECONDARY BACKING	-	Power Lock® High Performance Backing
ASTM E-648	-	Average Critical Radiant Flux: Greater than .45 - Class 1
NBS SMOKE CHAMBER TEST	-	Specific Optical Density: Less than 450
COORDINATE PRODUCTS	-	Foundation

WARRANTIES:

Wear Warranty	-	Useful Life
Static Warranty	-	Useful Life
Edge Ravel Guarantee	-	Useful Life
Delamination Guarantee	-	Useful Life
Recycling	-	Qualifies for Invista Reclamation Program

CRI INDOOR AIR QUALITY TESTING PROGRAM - PASSES - CERTIFICATION NO. 14222878

NOTES:

Chair pads are recommended under office chairs with roller casters to preserve appearance retention, act as a deterrent toward delamination and to avoid premature or accelerated wear. Clean Step® walk-off tiles by Blue Ridge or walk-off mats are recommended at building entryways to reduce soiling.

*Product specifications are derived from averages resulting from normal manufacturing tolerances in yarn, fiber, fabrication or finishing, and may vary within normal industry tolerances. Construction value quotes are "at point of manufacture". Performance is not affected by these variables.

As with all patterned carpet, a perfect pattern match may not be possible due to the fact that carpet is a textile subject to shrinking and expansion in both length and width. A plus or minus 1% should be expected. However, a reasonable pattern match may be achieved by competent installers using power stretching and stay nailing techniques.

Installation of pattern carpet requires more time to install correctly, which should be considered in the original installation quotation.